ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notification dated 22nd September 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 3 P.M. of 23rd October 1933, for the construction of a building for the Municipal High School at Dodballapur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 as earnest money, and be superscribed "Tender for constructing a building for the Municipal High School at Dodballapur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent of contractor's profit.

11. In all matter not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily be rejected.

Abstract estimate for the construction of two Blocks for the Municipal High School at Dodballapur.

No.	Items of work	Per	Rate	Contents	Total
			Rs. a. p.		Rs.
1	Earth-work excavation and filling in ...	C.yd.		178	
2	Concrete quartz metal in lime mortar ...	C.ft.		1,544	
3	Burnt size stone in lime mortar with bond stones.	„		3,518	
4	Burnt stone slabs 6″ thick one line dressed...	Sq.ft.		146	
5	Burnt stone pillars 2 line dressed with hole for angle iron brackets and notch for bessemer (15″ x 6″) 11½′ long.	No.		36	
6	Do 19 ft. long ...	„		16	
7	Masonry pillars (brick in mortar) square in section and complete with plastering (7′ x 1 1/8′ x 1 1/8′).	„		8	
8	Do (14′ x 1 1/8′ x 1 1/8′) ...	„		8	
9	Burnt brick in clay for superstructure (walls	C.ft.		2,662	

No.	Items of work	Per	Rate	Contents	Total
			Rs. a. p.		Rs.
10	Mangalore tiled roofing on teak wood reepers 2" x 1" with 2 ft. eave projection complete.	Sqr.		47·76	
11	Ridge tiles set in mortar and pointed with cement.	R.ft.		217	
12	Teak wood wrought and put up including wood oiling inside and painting for exposed faces (*i.e.*) outside the wall.	C.ft.		298	
13	Teak wood battened door with shutters 1" thick with fittings including iron clamps etc., complete with painting.	Sq.ft.		36	
14	Teak wood windows with battened shutter 1" thick in four halves with fittings including iron clamps and painting.	"		48	
15	Teak wood eave board plain 8" deep 1" thick with painting, etc., complete.	R.ft.		596	
16	Flooring with burnt stone slabs 3" thick on sand bed and pointed with cement.	Sqr.		23·76	
17	Cement pointing	"		4·84	
18	Teak wood reepers trellis work in teak wood frame, etc., complete as per design.	Sq.ft.		294	
19	Coping with brick in chunam and plastered one complete.	R.ft.		284	
20	Plastering with lime mortar 2 coats ...	Sqr.		57·88	
21	White washing 2 coats	"		57·88	
22	Angle iron cleats 4" x 4" x ½" and 4" long connected with one bolt to pillar and bessemer complete with painting and fixing complete.	No.		72	
23	Steel anchor rods for fixing hip rafters to pillars.	"		8	

M. A. SRINIVASACHARI,
Executive Engineer.

KADUR DIVISION.

Notification dated 29th September 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 24th October 1933, till 3 P.M., for maintenance work of Yegati tank, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 325 (three hundred and twenty five only) in cash or Government Promissory Notes as earnest money and be superscribed "Tender for maintenance work of Yegati tank," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures. Tenderers offering a percentage reduction on the estimate amount will be rejected.

10. Any rates for the lumpsum amounts for the items not called for if tendered by the tenderer will not be taken notice of.

11. There should be no corrections or erasers in the tenders and the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any noted in each page at the foot of the same by the tenderer.

12. When once the rates have been tendered they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be fixed by the Executive Engineer in accordance with schedule of rates is final and legally binding on the tenderer.

13. The contract should not be sublet.

14. In all matters of disputes of any kind not specially provided for in the agreement of rates, penalties, measurements quality of work, etc., the decision of the Superintending Engineer is final and legally binding.

15. No claim for damages for delays caused by the officers of the Department in the execution of the work will be considered whatever be the reason for such delays. Contractors should bear this in mind when tendering for the work.

16. The contractor should hold himself responsible for the good behaviour of his men of all grades towards the officers of this Department.

Abstract quantity of estimate of Yegati Tank Maintenance Work, Kadur Taluk.

No.	Particulars	Unit	Quantity	Rate	Words and figures
1	Earth work with cutting grips to Bund, watering and tamping, etc., complete including lead and lift.	Cyd.	9,330		
2	Gravel to be mixed with good earth and carried on top of bund including lead and lift.	„	5,822		
3	Turfing the slopes with good turfing Grass..	Syd.	18,867		
4	Jungle clearing and uprooting the roots in its entirety.	Lump sum			

Abstract Notification, dated 16th September 1933.

The attention of the public is invited to the notice calling for tenders for Reconstructing Girder Bridge in 6/16th mile of Bababudan Hill Road, published in extenso on pages 1173 and 1174, Part VI of the *Mysore Gazette*, dated 21st September 1933.

The earnest money to be deposited is Rs. 165 and the last date for receiving tenders is 16th October 1933 till 3 P.M.

Abstract Notification, dated 11th September 1933.

The attention of the public is invited to the Notice calling for tenders for Constructing Girder Bridge in 6/186th mile of Kadur-Mangalore Road, published in pages 1151 and 1152 of Part VI of the *Mysore Gazette*, dated 14th September 1933.

The last date for receiving tenders is 9th October 1933, till 3 P.M.

Earnest money to be deposited is Rs. 225 (Rupees two hundred and twenty-five only).

L. A. H. WINCKLER,
Executive Engineer.